

**POCATELLO/CHUBBUCK
SCHOOL DISTRICT NO. 25
Bannock County, Idaho**

INVITATION TO BID

**ASPHALT REMOVAL AND REPLACEMENT/ ASPHALT OVERLAY AND ASPHALT SEAL
COATING AT VARIOUS SCHOOLS**

Sealed bids will be received by a representative of the Board of Trustees of School District No. 25, Bannock County, Idaho at 3115 Poleline Road, Pocatello, Idaho, 83201, until 11:30 a.m., April 28, 2016, for Asphalt Removal and Replacement/ Asphalt Overlay and Asphalt seal Coating at Various Schools.

Specifications or additional details, (including bid forms), may be secured at 3115 Poleline Road, Pocatello, Idaho, 83201. A pre-bid conference will be held at 2:00 p.m. on Wednesday, April 20, 2016, at the Maintenance Department, 185 Maple St Pocatello, Idaho 83201. All bids must be on the forms furnished, all blank spaces filled in, and signed with the name and address of the Bidder. No unqualified bids will be read.

Each bid shall be accompanied by a certified check, cashier's check, or a bidder's bond, (executed by a qualified surety company with the power to do business in the State of Idaho), in the sum of not less than five percent (5%) of the total bid, made payable to School District No. 25, Pocatello, Bannock County, Idaho. This surety shall be forfeited by the bidder in the event of failure to enter into a contract. Compliance with Idaho Public Works Law is required. Personal or Company checks will not be accepted.

The Board of Trustees reserves the right to reject any/or all bids, or to waive any informalities, or to accept the bid or bids deemed best for School District No. 25, Pocatello, Bannock County, Idaho.

Paul Vitale, Clerk
SCHOOL DISTRICT NO. 25

To be published on the dates of:

April 14, 2016
April 21, 2016

IDAHO STATE JOURNAL

BID EVALUATION CRITERIA:

Contractor selection on this project will be evaluated based on the following:

- 1) Price;
- 2) Contractor reputation for quality of work with current customers or past performance with District 25. (Please list all asphalt jobs/contracts greater than \$10,000 performed in the past two years if contractor has not performed one for the District in past 5 years);
- 3) Vendor ability to best match the listed criteria as specified.

GENERAL SPECIFICATIONS

ASPHALT PATCHING

SCOPE OF WORK - The contractor shall furnish and install all materials, labor, equipment, and other necessary items for the installation of the asphalt paving as specified herein.

The asphalt paving shall be installed in the areas in strict accordance with specifications A-2 of the Asphalt Institute to a thickness of two or more inches as specified and all materials and methods of preparation shall conform to the requirements of these specifications.

Preparation of Existing Asphalt Paving Grounds - The entire existing asphalt paving grounds shall receive pavement as called for within these specifications. The patch areas shall be cut out in a straight line. All pot holes and low spots shall be prepared and brought to level with asphalt patch, SS-1H tack coat. Low areas next to buildings are to be raised to provide proper drainage away from buildings. Areas adjacent to walls, lawns, and curbs shall be tapered down to the finish grade so that the two inch asphalt concrete mat does not extend above the adjacent concrete or lawn. If unusual excavating conditions are encountered, stop work and notify owner.

The grounds that call for asphalt overlay shall be covered with an asphalt mat to a thickness of two or more inches. This mat shall be laid in strict accordance with these specifications and with specifications A-2 of the Asphalt Institute. The asphalt paving mixture shall be mixed in a batching plant which has the approval of the State of Idaho Highway Department.

The maximum size of aggregate to be used in the Asphalt concrete mixture shall be 5/8" or 1/2" fine material, and shall be well graded to the point where 0.8% will pass a No. 200 sieve. The aggregate with the asphalt cement shall be mixed in the batching plant and heated to a temperature of 300 degrees F. and shall be delivered to the job and placed at a temperature of not less than 225 degrees F.

The mixture shall be spread with a power screed, where possible, which shall spread the mix evenly over the compacted sub-base. The mat shall then be rolled with power roller weighing not less than ten tons. The thickness of the mat after rolling shall be one or two or more inches as specified and shall not vary in thickness more than 1/4" either way from the specified thickness. Any low spots shall be immediately remedied by cutting out the course at such spots and replacing it with fresh, hot mixture which shall be immediately compacted to conform to the surrounding area.

DESCRIPTION - This item shall consist of asphalt patching in those areas disturbed in the existing street by the contractor's construction activities, as well as for matching back purposes where radii are changed, or blending into new curb and gutter, alleyways, etc. Asphalt patching shall be in conformance with these specifications and the specific type of patching material used shall be approved by the School Plant Coordinator.

CONSTRUCTION METHODS AND MATERIALS

(a) **General Construction:** Asphalt patching shall be under the direction of the School Plant Coordinator.

(b) **Equipment:** The contractor may use any type of mixing, spreading, hauling, compacting, etc. equipment he may desire or has at his disposal provided the equipment is in satisfactory condition, is of the correct type for the job, and is of such capacity that the construction schedule can be maintained unless construction conditions or situations prevent or restrict usage of the equipment as to size, weight, or its ability to be detrimental to existing topography, structures, utilities, etc. while working.

(c) **Asphalt Patching I:** Asphalt patching shall consist of placement of 4" of 3/4" crushed aggregate and 3" of hot mix mat with all depths understood to be compacted depths. Prior to placing the patching profile the existing material shall be compacted. The contractor shall seek approval from the School Plant Coordinator of his patching material and method prior to actual placement.

(d) **Asphalt Patching II:** Asphalt patching shall consist of placement of geotextile fabric 2002, 12" of 2" minus sub-base aggregate, 3" of 3/4" crushed aggregate and 3" of hot mix mat with all depths understood to be compacted depths. Prior to placing the patching profile the existing material shall be compacted. The contractor shall seek approval from the School Plant Coordinator of his patching material and method prior to actual placement.

Contractor shall cut the existing asphalt in straight lines; remove the asphalt and base material to match the profile of the patching specification.

All areas to be patched shall be kneaded up exposing a good edge. The fabric shall be placed, and then granular material shall then be placed and compacted. Next, the existing oil mat edge shall be cleaned and tack-coated and the asphalt material laid in, compacted and blended into the existing old oil or curb and gutter edge, etc., making a presentable and durable patch.

Asphalt patching will not be done on poor sub-grade conditions and it shall be up to the determination of the School Plant Coordinator if such conditions are encountered of how and by what means the condition or situation can be rectified.

METHOD OF MEASUREMENT

Asphalt patching shall be measured by the square foot for each square foot of pavement placed and compacted in the areas shown on the plans or as directed by the School Plant Coordinator.

BASIS OF PAYMENT

The accepted quantity of this item will be paid for at the contract price per unit completed as called for on the proposal sheet, which price shall be full compensation for the furnishing of all materials, labor, equipment, tools, or any other work necessary to complete this item in conformance with the plans and these specifications or as directed by the School Plant Coordinator.

PROJECT No. 1 – Highland High School Asphalt Patching II, 1800 Bench Rd.

DESCRIPTION OF WORK: Approx. – One area 450sf of Asphalt Patching II (Area of construction to be determined at walk-thru and as indicated on attached plans)

Contractor shall use specification for Asphalt Patch II where required.
Contractor shall use specification for Asphalt Patch I where required.
Contractor shall sweep and clean asphalt roadways of all dirt and debris.
Contractor shall remove all excess materials from job site leaving job clean and presentable.

All area dimensions are approximate and not intended to be precise. In order to reduce or eliminate change orders, it will be necessary for the bidder to complete field verification of site and dimensions

PROJECT No. 2 – Highland High School Seal Coating, 1800 Bench Rd.

DESCRIPTION OF WORK: Approx. – 286,293sf

Contractor shall clean and sweep area of all dirt and debris to be seal coated.
Contractor shall rout cracks to 3/16 inch wide minimum. Rout larger cracks containing vegetation to minimum of one inch deep. Crack sealant applied minimum 3405 Federal Specifications. Product shall be Maxwell or equal.
Contractor shall furnish and install (2) coats asphalt slurry seal on entire area, as per manufacturer's recommendations. (Tuff-Coat or equal)
Contractor shall sweep and clean area of all dirt and debris.
Contractor shall remove all excess materials from job site leaving job clean and presentable.
Contractor shall re-paint the parking lines, numbered parking stalls and Handicapped Logo's. Acrylic Waterborn traffic paint, 4 inch yellow line (2) coat system.

All area dimensions are approximate and not intended to be precise. In order to reduce or eliminate change orders, it will be necessary for the bidder to complete field verification of site and dimensions

PROJECT No. 3 – Alameda Middle School Asphalt Patching II, 845 McKinley

DESCRIPTION OF WORK: Approx. – Asphalt Patching II (Area of construction are three options as indicated on attached plans)

- Area A – approx. 3,500sf**
- Area B – approx. 5,525sf**
- Area C – approx. 7,460sf**

Contractor shall use specification for Asphalt Patch II but no new subbase is to be figured for this work.
Contractor shall remove existing asphalt and install gravel as needed to allow for paving to be installed at original grades before overlays. Once existing asphalt is removed, Contractor will proof roll existing subbase and soft spots will be dealt with at that time.
Contractor shall sweep and clean asphalt roadways of all dirt and debris.
Contractor shall remove all excess materials from job site leaving job clean and presentable.

All area dimensions are approximate and not intended to be precise. In order to reduce or eliminate change orders, it will be necessary for the bidder to complete field verification of site and dimensions

PROJECT No. 4 – Jefferson Elementary School Asphalt Patching II, 1455 Gwen Dr.

DESCRIPTION OF WORK: Approx. – Three areas 949sf of Asphalt Patching II (Area of construction to be determined at walk-thru and as indicated on attached plans)

Contractor shall use specification for Asphalt Patch II.
Contractor shall sweep and clean asphalt roadways of all dirt and debris.
Contractor shall remove all excess materials from job site leaving job clean and presentable.

All area dimensions are approximate and not intended to be precise. In order to reduce or eliminate change orders, it will be necessary for the bidder to complete field verification of site and dimensions

PROJECT No. 5 – Jefferson Elementary Seal Coating, 1455 Gwen Dr.

DESCRIPTION OF WORK: Approx. – 76,356sf

Contractor shall clean and sweep area of all dirt and debris to be seal coated.
Contractor shall rout cracks to 3/16 inch wide minimum. Rout larger cracks containing vegetation to minimum of one inch deep. Crack sealant applied minimum 3405 Federal Specifications. Product shall be Maxwell or equal.
Contractor shall furnish and install (2) coats asphalt slurry seal on entire area, as per manufacturer's recommendations. (Tuff-Coat or equal)
Contractor shall sweep and clean area of all dirt and debris.
Contractor shall remove all excess materials from job site leaving job clean and presentable.
Contractor shall re-paint the parking lines, ***numbered parking stalls*** and Handicapped Logo's. Acrylic Waterborn traffic paint, 4 inch yellow line (2) coat system.

All area dimensions are approximate and not intended to be precise. In order to reduce or eliminate change orders, it will be necessary for the bidder to complete field verification of site and dimensions



BIDDER CERTIFICATION FORM

1. **Debarment and Suspension** – In submitting this bid proposal, we hereby certify that we have not been suspended or in any way excluded from Federal procurement actions by any Federal Agency. We fully understand that if information contrary to this certification subsequently becomes available, such evidence may be grounds for non-award or nullification of a bid contract.
2. **Anti-Collusion** – In submitting this bid proposal, we hereby certify this proposal was developed and prepared without any collusion with any competing bidder or District employee. The content of this proposal has not been disclosed to any competing or potentially competing bidder prior to the proposal due date and time. Furthermore, no action to persuade any person, partnership or corporation to submit or withhold a bid has been made.
3. **Anti-Lobbying** – In submitting this bid proposal, we hereby certify that to the best of our knowledge and belief, no appropriated Federal funds have been paid or will be paid by or on behalf of person associated with this proposal to any person for influencing or attempting to influence and officer or employee of any agency, a member of Congress, an office or employee of Congress or an employee of a member of Congress in connection with the awarding of any Federal contract, the making of any Federal grant, the making of any Federal loan, the entering into of any cooperative agreement and the extension, continuation, renewal, amendment or modification of any Federal contract, grant, loan or cooperative agreement.
4. **National Sexual Offender Registry** – In submitting this bid proposal, you certify to the District that your company will prohibit any persons in your employ who are registered or required to register under the Idaho Sex Offender Registration Act from participation in company business with the District if such participation would require them to be present on school property. You certify further that you have cross checked such employees against the National Sex Offender Registry found at the following web link: <http://www.nsopr.gov/>

Signed: _____

Name & Title: _____

Company: _____

Address: _____

City & State: _____

Date: _____

BID RESPONSE SHEET

Board of Trustees
School District No. 25
3115 Pole Line Road
Pocatello, ID 83201

Date: _____

We, _____ propose to furnish all labor, materials, tools, and equipment and complete all work called for by these specifications in connection with Asphalt Removal and Replacement/ Asphalt Overlay and Asphalt Seal Coating at Various Schools under the supervision of the School Plant Coordinator, for the sum of:

- PROJECT No. 1 Highland High School – Asphalt patch \$ _____**
- PROJECT No. 2 Highland High School – Seal Coating \$ _____**
- PROJECT No. 3 Alameda Middle School – Asphalt replacement**
 - Area A \$ _____**
 - Area B \$ _____**
 - Area C \$ _____**
- PROJECT No. 4 Jefferson Elementary School – Asphalt pat. \$ _____**
- PROJECT No. 5 Jefferson Elementary School – Seal Coat \$ _____**

Cost of Asphalt Patching I per sq. ft. _____

Cost of Asphalt Patching II per sq. ft. _____

Work can begin June 6, 2016 and must be completed by August 1, 2016.

Owner reserves the right to do all the projects or only the projects that fit within our budget. Bids will be awarded to the lowest responsible bid for each Project.

Workers Compensation & Employee Liability Insurance: Expiration Date: _____

CONTRACTOR'S ADDRESS & LICENSE NUMBER:

_____ Name	_____
_____ Address	Public Works Contractor License Number
_____ City, State Zip	_____
_____ Date	Authorized Signature and Title
_____ Phone	
_____ Fax	_____ FEIN #

Attached, if applicable, is a listing of subcontractors names and addresses which will be used for this project.

Attached is our Affidavit of Alcohol and Drug-Free Worksite, as pursuant to Idaho Code 72 - 1717.

CONTRACTOR'S AFFIDAVIT
CONCERNING ALCOHOL AND DRUG-FREE WORKPLACE

STATE OF _____

COUNTY OF _____

Pursuant to the Idaho Code, Section 72-1717, I, the undersigned, being duly sworn, depose and certify that named contractor is in compliance with the provisions of Idaho Code section 72-1717; that named contractor provides a drug-free workplace program that complies with the provisions of Idaho Code, title 72, chapter 17 and will maintain such program throughout the life of a state construction contract and that named contractor shall subcontract work only to subcontractors meeting the requirements of Idaho Code, section 72-1717(1)(a).

Name of Contractor

Address

City and State

By: _____
(Signature)

Subscribed and sworn to before me this _____ day of _____, _____.

Commission expires:

NOTARY PUBLIC, residing at
