

ADDENDUM NO.1

March 9, 2017

FRANKLIN MIDDLE SCHOOL BOILER REPLACEMENT

The data included hereinafter is issued by the Engineer (Engineered Systems Associates, 1355 East Center, Pocatello, ID 83201) as clarification, addition to, and/or deletion from the Drawings, Specifications, and Contract Documents relative to the above-named project.

Except as affected by data included hereinafter, all other parts of the Contract Documents shall remain in full force and effect as issued by the Engineer. It shall be the sole responsibility of the Bidder to appropriately disseminate this data to all concerned prior to the assigned bid time and date. Receipt of the addendum shall be recorded by the Bidder in the appropriate space on the Bid Form included in the Contract Documents.

1. See Attached List of Pre-Bid Walk Through Attendees.
2. Specifications:
 - a) Section 23 0502 Demolition. The School District will remove any equipment and material they want to salvage before the Contractor starts. All other equipment and material (as shown being demoed on Drawings) shall be disposed of properly by the contractor.
 - b) Section 23 5230 Gas Boiler. The School District has requested Laars Boilers as per the schedule to match other existing Boilers in the District. No other Boilers will be considered.
3. Drawings:
 - a) Sheet C1.0. Circulating Pump Schedule. CP-1, 2, 3 Shall be 2.0 H.P. CP-4, 5 shall be 10 H.P.
 - b) Sheet ME1.1: New Water Heaters to be mounted on Uni-strut on concrete wall. Place 2" Blueboard Insulation behind Water Heaters and Piping to protect from cold.
 - c) Sheet ME1.1. New pumps to be set on New 4" Concrete Housekeeping Pads, or locate pumps on Existing Boiler Pad. Modify Piping as required.
4. Prior Approvals:
 - a) Pumps: Taco, Armstrong.
 - b) Hydronic Specialities: Wingert, Wheatley, Titan, Taco, Miljoco, Twin City Hose, Vibro Acoustics, Engineered Flex Products, Nexus.
 - c) Instantaneous Water Heater and Tank: Laars.
 - d) VFD's: Danfoss.

END OF ADDENDUM

